

REPLY TO PRE-BID MEETING QUERIES		
<b>Name of Work:</b>	Supply, Installation, Testing & Commissioning of Networking with Optical Fiber Cables (OFC) including Closed Circuit Television (CCTV) Camera Works at Phase 1C & 1B Area” in Origins, Chennai	
<b>Date:</b>	20.12.2024; 11.00 A.M. to 1.00 P.M.	
<b>Participants:-</b>		
<b>Bidders</b>	(1) Laurel Communication; (2) Finecom Communication; (3) HR Infotech Networking & Electrical Services; (4) VJ Network; (5) La Crescendo; (6) Cosmogenic IT Solutions.	
<b>MIPCL</b>	K.SenthilSai [Contracts] / C.Amal [IT-MWCDL] / Srirangan Kiran [MIPCL]	
<b>MLDL (CCT, Pune &amp; Mumbai)</b>	Swamy Anthony [Contracts-MEP] / G.P.Shreekanth Rao	
<b>ACE [Consultants]</b>	M.Suresh	
<b>Key Bidders Queries:-</b>		
	<b><u>Bidders Query:-</u></b>	<b><u>Consultant/MIPCL Reply:-</u></b>
1	Camera Type to be confirmed.	Camera type should be 'Fixed Type with Project Model Bullet Type Camera' of 'Equation' brand and NVR to be considered.
2	Boq Item No. 14, Which type of POE with wattage to be considered	The POE switch with suitable wattage to be considered.
3	Bidders requested for additional approved makes for 'HDPE' pipes to be considered, which are easily available in local market.	MIPCL confirmed to consider 2 more approved makes for HDPE pipes as per specifications mentioned in the BoQ & they are: <b>(i) Reliance &amp; (ii) Supreme makes.</b>
4	Bidders asked the procedure for laying HDPE inside the Telecom Duct.	The HDPE pipe should be fixed on the side walls of the telcom duct with proper clamps at every 1.0 m interval.
5	Bidders requested for details regarding Earthing Arrangement.	The pipe earthing should be done as per 'IS 3043' with necessary earth pit chamber.
6	Bidders asked details reg. Main Incoming Power for the racks.	The main incoming supplies shall be provided by Developer (MIPCL).
7	<b><u>Amendment to 'Payment Terms':-</u></b>	
7.1	Applicable for 100% 'Supply Items' (and) for 'Supply cum Installation Items'	60% against Supply of Materials at site. 20% against completion of Installation. 10% against Commissioning & 10% against Handing Over.
7.2	Applicable for 100% 'Installation items'	80% against Completion of Installation. 10% against Commissioning & 10% against Handing Over.